

Paul Nunn Roofing Ltd

NEW ROOFS RE-ROOFING FLAT ROOFING LEAD ROOFING

Woodlarks, Flempton Bridge Carr, West Stow,
Bury St Edmunds, Suffolk, IP28 6ER
Tel/Fax: 01284 728378 Mobile: 07850 916218
www.PaulNunnRoofing.co.uk
info@paulnunnroofing.co.uk

QUOTATION

M^r BRIAN ROBERTS
PRITHIPURA
LOWER FARM ROAD
RINGSHALL
IP14 2JE

2/9/2020

REF – REROOFING TO – RINGSHALL VILLAGE HALL

To supply & fix the following materials for completion of reroofing

Supply & fix independent scaffolding for access to roof
Supply skips for all rubbish
Carefully strip off existing clay pantiles & stack for reuse
Remove existing battens & underlay & dispose of into skip
Denail exposed rafters & denail
Supply & fix Ruberoid 5u hyload eaves felt draped into guttering
Cover the whole roof with Klober Permo breathable underlay
Supply & fix new 25 x 50mm treated sawn graded battens fixed at a gauge to suit tiles,
Replace existing lead valleys with new 450mm code 5 lead sheet
Supply & fix 150mm fibre cement undercloak to all verges
Supply & fix universal eaves comb to top of fascia boards
Retile with existing tiles replacing any defective tiles with reclaimed to match,
Allowance has been allowed for replacing area of tiles that are a different pattern on rear sloping roof,
Rebed existing ridge tiles making up shortfall with reclaimed to match,
On completion of works remove scaffolding & leave clean & tidy,

SUB TOTAL £ 27,169.00p + VAT

ROOF REPAIRS TO VALLEYS

To supply tower scaffold for access
Remove existing tiles from two valleys
Replace existing lead with new code 5 lead sheet & rebed tiles,
Replace section of tiling to roof slope with tiles to match existing

SUB TOTAL £ 3,482.00p + VAT



Directors: P. Nunn • X. A. Ριζηγορόπουλος (Χορηγούσα Σύμβουλος) Ριζηγορόπουλος